



HCAL Status

CMS HCAL Status

Jim Freeman




Outline

- **Absorber**
- **Optics**
- **Status at CERN**
- **HPDs**
- **Front End Electronics**
- **Higher Level readout**
- **Radioactive Source Test Milestone**
- **HF**
- **Summer 2002 Testbeam**
- **Longer Term Schedule**



HB wedge design

Towers and Scintillator Layers





Absorber

HB- at SX5 at CERN →

- 17 HB+ wedges at CERN in Building 186. (Wedge 16 being repaired)
- Optics installed, QC Testing in progress





HB Wedges at Bldg 186





HB- wedge 16 Damage






HE + at Minsk





Megatile design, top view


LAYER 11 MEGATILES, TOP VIEW



Components are the machined scintillator plates, cover plates, fiber assembly (WLS spliced to clear fiber, optical connector) pigtails




Megatile cross-sectional view





Protvino - Pig Tail QC



RMS of the light yield transmission is less than 5%.




Megatile Manufacture -HE



10 megatiles/day at Protvino



HB Megatile Production





Installation at CERN





Optics Factory at FNAL

- **HB Optics factory in final phase. Will be finished in 2 weeks.**
- **Reduce staffing from 13 to 5.**
- **Factory will redirect to work on components for RBX's, HV, LV, electronics components.**




HPD Delivery Schedule

Letter of Intent received by DEP Oct 12, 01

Spare Tubes (20)	Dec 20, 01
Spare Tubes (30)	Mar 1, 02
HB- (72)	May 12, 02
HE- (72)	Aug 23, 02
HB+ (72)	Nov 3, 02
HE+ (72)	Jan 28, 03
HO (146)	Jun 23, 03

So far, 20 at Minnesota. ~ on schedule

First Production HPD







HPD Anti-Reflective Coating

3 layer coating on top of HPD Diode.

New Diode Structure





RBX Status

- **HB RBX in production (Mississippi). Should be complete by April 02.**
- **ODU's for HB complete (Notre Dame) 2-3% rms.**
- **HE RBX in design. Design should be complete by April 02**
- **Production of HE RBXs late spring**
- **HE ODUs to be built in ND factory in summer.**
- **Design HO RBX. Build over summer**
- **HO ODUs in fall (ND)**



HB RBX Assembly




Full RBX with
19 ch RMs

RBX Interior -- HV
distributor and
backplane




Readout Module (RM) Overview





RBX Readout Module

- The readout module (RM) integrates the HPD, front end electronics, and digital optical drivers.








ODU production at Notre Dame






ODU QC






FE/DAQ Readout





FE Channels



T. Shan
4/1/02



FE Status

Past 6 months

- Tested proto CCA Asic – looks good
- Tested proto QIE Asic
 - Does not run at 40MHz (easy fix)
 - Noise levels under study
 - 3000e- rms with soldered coax connections btw HPD and QIE
- HB Backplane layout complete
- Proto GOL (serializer) tested - OK
 - Gigabit Ethernet protocol
 - 1600 Mbits/s
- Proto VCSEL and custom package tested – ok
- Rad qualified “glue” logic parts



CMS QIE Status

Full chip submitted 3/13/01

Received 5 wafers 6/1/01

Testing shows chip fully functional

- **Chip does not run at 40 MHz**
- **Noise as a function of input capacitance being studied**
- **Noise of 3000e- rms achieved with soldered coax connections btw HPD and QIE**

**Goal is to submit production part by
April '02**



CCA Status

CCA submitted June 25, 2001

25 parts back Oct 11, 2001


Chips under test

- Problem with reads/writes to internal registers
- Problem with writes fixed with repair on chip (jumped out inverter)
- Problem with reads under study
- Other than reads, the CCA appears to be fully functional

Engineering run chip submitted on Feb 11. Due back April 8.



CCA ASIC Repair






Radioactive Source Vertical Slice

- **Exercise a single channel of HCAL readout from scintillator to computer**
 - Radioactive Source
 - Scintillator
 - Optical Fiber
 - HPD
 - QIE
 - Digital optical readout
 - HTR
 - DCC
 - Computer
- **First complete ~40Mhz readout of HCAL Channel**
- **Successful demonstration of radioactive source measurement for calibration.**



QIE under test





TTCrx
Clock
distributor

QIE
Test
Board



DAQ System







Radioactive Source Test

Response as source is removed from scintillator

mean (channels)



HTGZ_01 @ mhlfnote
Run 10269, Ch. B, all Caps





HF Status

- **10 HF absorber wedges finished. 5 at CERN**
- **Fiber ordered. First delivery to CERN**
- **Phototubes ordered.**
- **Expect first complete wedge (fibers, pmts) at CERN in early June 02.**
- **Expect to test in H2 test beam this summer.**




First Production HF Wedge





Idea to use HO for muon trigger, vertical slice trigger

HO (tower No.1) occupancy: muons vs noise



Expect ~ 2 p.e. of noise and ~ 8 p.e. of signal for a single muon at normal incidence.

Toy monte Carlo with 5000 e- noise, 8 pe/mip in HO



Testbeam Motivation

- **HB- assembled in September 01**
- **HB+ will be assembled in September 02**
- **Only chance for testing production wedges with fast (engineering run ASICS) electronics is Summer 02.**
- **Desire to test 2 to 4 production wedges from HB+.**
- **Get absolute calibrations to carry from H2 to UX5.**



Testbeam Goals

- Prepare test beam DAQ to read out prototype HTR cards.
- Electronics will be 6-channel RBX cards, using first run QIE and engineering run CCA. GOL and fiber-optic readout.
- Rochester ECAL module on table, with new motion mechanism.
- Take ~ 4 production wedges into beam.
- Measure radioactive source fingerprints.
- Scan with pions as function of eta and phi.



Testbeam Responsibilities

- **H2 Test beam beamline, DAQ – Laza**
- **RBX FE cards – Terri Shaw**
- **RBX mechanics, optics – Randy Ruchti**
- **Check out / test RBX's – Anatoly Ronzhin**
- **System integration FE card to HTR – Jim Rohlf**
- **Radioactive source system – Virgil**
- **Calibration System --Vasken, Sergey Los**
- **Refurbish table – George Ginther**
- **ECAL Module, new motion – Pawel**
- **HV System – Sergey Los**
- **HPD checkout and setup – Arjan Heering**



Testbeam Conclusions

- **Test Beam 2002 very important goal for HB group.**
- **Only chance to test production wedges**
- **Important step in system integration in preparation for SX5 activities in late 02, early 03.**



Conclusions

- **HCAL absorber and optics making good progress**
- **Front end and Higher level electronics progressing**
- **Finished with absorber, optics.**
- **HPDs under control**
- **ASICs under control**
- **HF fibers and pmts ordered.**
- **Looking forward to test beams in summer 02**
- **Install electronics Spring 03**
- **Vertical Slice Tests in SX5 in 03**